


SUPERPAC

6 AT A TIME



INSTALLATION 466371F9901

SEPTEMBER 2000 • US\$250

World Headquarters
801 Johnson St. • Alpena, Michigan, 49707 • U.S.A. Phone (517) 354-4111

BESSER

COMPANY NAME:	
SERIAL NUMBER:	
Assembly Number:	
WIRING DIAGRAM NUMBER:	
Installation Drawing Number:	



SUPERPAC TABLE OF CONTENTS

	LIST OF TABLES	.ii
	LIST OF ILLUSTRATIONS	
	SAFETY BULLETIN	
	SAFETY SIGNS	
	SPECIFICATIONS	.vi
PREP	PARATION	
	PREPARING THE LOCATION OF THE SUPERPAC	-1
MACH	HINE HANDLING1	-6
INSTA	ALLATION	
	TO INSTALL A SUPERPAC	-8



SUPERPAC LIST OF TABLES

SPECIFICAT	TIONS	
Α	STEEL PALLET SPECIFICATIONS	vi
В	SUPERPAC ELECTRICAL DATA	vii
С	SUMMARY OF ACOUSTICS	ix
PREPARATI	ON	
1.	1 I-beam Dimensions	1-2
	SUPERPAC	
	LIST OF ILLUSTRAT	IONS
PREPARATI	ON	
1.	1 Side Elevation	1-1
1.	2 Front Elevation	1-2
1.	o =	
1.	4 Top View	1-4
MACHINE H	ANDLING	
1.	5 Machine Handling	1-6
INSTALLATI		
1.	6 Typical Superpac Installation	1-7
1.	7 Right Side Elevation	1-8
1.	• =	
1.	9 Pour Non-Shrink Grout Inside	1-10
1.	10 Air Supply Connections	1-11



SAFETY BULLETIN

This notice is issued to advise you that some previously accepted shop practices may not be keeping up with changing Federal and State Safety and Health Standards. Your current shop practices may not emphasize the need for proper precautions to insure safe operation and use of machines, tools, automatic loaders and allied equipment and/or warn against the use of certain solvents or other cleaning substances that are now considered unsafe or prohibited by law. Since many of your shop practices may not reflect current safety practices and procedures, particularly with regard to the safe operation of equipment, it is important that you review your practices to ensure compliance with Federal and State Safety and Health Standards.

IMPORTANT

The operation of any machine or power-operated device can be extremely hazardous unless proper safety precautions are strictly observed. Observe the following safety precautions:

- Always be sure proper guarding is in place for all pinch, catch, shear, crush and nip points.
- Always make sure that all personnel are clear of the equipment before starting it.
- Always be sure the equipment is properly grounded.
- Always turn the main electrical panel off and lock it out in accordance with published lockout/tagout procedures prior to making adjustments, repairs, and maintenance.
- Always wear appropriate protective equipment like safety glasses, safety shoes, hearing protection and hard hats.
- Always keep chemical and flammable material away from electrical or operating equipment.
- Always maintain a safe work area that is free from slipping and tripping hazards.
- Always be sure appropriate safety devices are used when providing maintenance and repairs to all equipment.

- A Never operate equipment unless proper maintenance has been regularly performed.
- ⚠ Never operate any equipment if unusual or excessive noise or vibration occurs.
- A Never operate any equipment while any part of the body is in the proximity of potentially hazardous areas.
- ⚠ Never use any toxic flammable substance as a solvent cleaner.
- A Never allow the operation or repair of equipment by untrained personnel.

It is important that you review Federal and State Safety and Health Standards on a continual basis. All shop supervisors, maintenance personnel, machine operators, tool operators, and any other person involved in the setup, operation, maintenance, repair or adjustment of Besser-built equipment should read and understand this bulletin and Federal and State Safety and Health Standards on which this bulletin is based.

466371F9901US F1 12SE00



SAFETY SIGNS

Sign	Description	Required
1	Electric Motor	
2	All Machines	
	All Panels	
3	Mixer	
4	Block Machine	
	SF-7 Cuber	
	BTO-6	2
	Overhead Block Transfer	3
	Depalleter	2
	AF-7 Block Pusher	2
5	Concrete Products Machine	1
6	Concrete Products Machine	1
7	Concrete Products Machine	2
8	Besser-Matic	4
9	Besser-Matic	4
10	Pallet Transport System	4
11	LSC-40A	4
	Overhead Block Transfer	4
12	Conveyors	6
13	SF-7 Cuber	8
14	AF-7 Block Pusher	2
	Pallet Transport System	4
15	All Machines	1
	All Panels	1
16	SF-7 Cuber	3
	AF-7 Block Pusher	2
	Slat Conveyors	2

To order safety decals, contact your local Besser representative or the Besser Central Order Department.

Thank you!





Large 113236F0409
High Voltage
Width 4 1/2 inch
Height 9 5/8 inch
Small 113236F0204
High Voltage
Width 2 inch
Height 4 1/8 inch



113237F0410 Mixer Blade Hazard Width 4 1/2 inch Height 1/4 inch



113240F0307 Crush Hazard Width 3 1/2 inch Height 7 1/2 inch



114692F1006 Nip Points Width 5 3/4 inch Height 9 1/2 inch



114688F0906 Crush Hazard Width 6 1/4 inch Height 9 1/2 inch



114689F0804 Fall Hazard Width 4 1/2 inch Height 7 3/4 inch





114690F0805 Falling Objects Width 4 3/4 inch Height 8 inch



114691F1006 Shear and Fall Hazards Width 5 3/4 inch Height 9 3/4 inch



113242F0409 Crush Hazard Width 4 1/2 inch Height 9 5/8 inch



113243F0410 Falling Objects Width 4 1/2 inch Height 10 inch




Vertical: 113245F0704 Horizontal: 113245F1005 Crush Hazard Vertical: Width 4 1/8 inch Vertical: Height 7 inch Horizontal: Width 10 inch Horizontal: Height 5 3/4 inch



Safety instructions decal-Suggested Lock-out procedure Width 4 inch Height 10 inch






113238F1005 Crush Hazard Width 10 inch Height 5 3/4 inch



113239F0604

Crush Hazard Width 6 5/8 inch Height 4 inch



113241F0605 Crush and Pinch Points Width 6 5/8 inch Height 4 inch



113246F0704

Nip Hazard Width 7 inch Height 4 1/2 inch



113247F1006 Crush Hazard Width 10 inch Height 6 inch



Crush and Pinch Points Hazard Width 10 inch Height 6 inch



SPECIFICATIONS

TOTAL WEIGHT: 67,800 Lbs [30754 Kg]

MAXIMUM MOLD WEIGHT: 6,000 Lbs [2727 Kg]

AIR LINE FITTING DIMENSIONS: 3/4" [19mm] I.D.

MINIMUM AIR PRESSURE: 80 psi [5.5 bars]

NOISE RATING: 102 to 114 DBA


MACHINE SPEED: up to 9 cycles / minute

PRODUCTION CAPACITY: up to 3240 blocks / hour

MINIMUM PRODUCT SIZE REQUIREMENT: 2" high [51mm]

MAXIMUM PRODUCT SIZE REQUIREMENT: 12" high [304.8mm]

PALLET REQUIREMENTS:



WIDTH & DEPTH = Actual size of steel pallet.

XMAX & YMAX = Maximum production area of steel pallet.

WIDTH	DEPTH	THICK.	X	Υ	PALLET NO.			
42.0" [1067mm]	20.5" [521mm]	.625" [16mm]	41.0" [1041mm]	19.5" [495mm]				
52.0" [1321mm]	18.5" [470mm]	.625" [16mm]	51.0" [1295mm]	17.5" [445mm]	470750F0021			
52.0" [1321mm]	19.5" [495mm]	.625" [16mm]	51.0" [1295mm]	18.5" [470mm]	470750F0022			
52.0" [1321mm]	20.5" [521mm]	.625" [16mm]	51.0" [1295mm]	19.5" [495mm]	470750F0023			
55.0" [1397mm]	18.5" [470mm]	.625" [16mm]	54.0"[1372mm]	17.5" [445mm]	470750F0024			
55.0" [1397mm]	20.5" [521mm]	.625" [16mm]	54.0"[1372mm]	19.5" [495mm]	470750F0025			
42.0" [1067mm]	18.5" [470mm]	.625" [16mm]	41.0" [1041mm]	17.5" [445mm]	470750F0026			
52.0" [1321mm]	18.5" [470mm]	.625" [16mm]	51.0" [1295mm]	17.5" [445mm]	470750F0027			
52.0" [1321mm]	20.5" [521mm]	.625" [16mm]	51.0" [1295mm]	19.5" [495mm]	470750F0028			
THICKNESS TOLERANCE: -0.010" [0.25mm] / +0.030" [0.76mm]								

Table A STEEL PALLET SPECIFICATIONS.



Specifications

SUPERPAC ELECTRICAL DATA

PLANT POWER SUPPLY (VOLTS)	Total Horsepower (HP)	Total Kilowatts (Kw)	CONTROL PANEL TRANSFORMER (VOLT-AMPS)	BRANCH CIRCUIT DISTRIBUTION SWITCH (AMPS)	BRANCH CIRCUIT FUSE FRS-R (AMPS)	Branch Circuit Feeder THHN	Branch Circuit Feeder Conduit	SHORT CIRCUIT INTERRUPTING CAPACITY (AIC)
220V-240V 50/60 Hz	50.5	37.6	1500	200	200	2 AWG 67.5мм²	1.5 IN. 38мм	200,000
380V 50 Hz	50.5	37.6	1500	200	150	2 AWG 33.6мм²	1.0 in. 25мм	200,000
415V 50 Hz	50.5	37.6	1500	200	125	3 AWG 26.7мм²	1 іN. 25мм	200,000
440V-480V 50/60 Hz	50.5	37.6	1500	100	100	4 AWG 21.6мм²	1 іN. 25мм	200,000
575V 60 Hz	50.5	37.6	1500	100	80	6 AWG 13.3мм²	0.75 in. 20мм	200,000

Table B SUPERPAC ELECTRICAL DATA.

Please consult the table above to find the appropriate electrical data for your SUPERPAC. First, find your corresponding plant power supply in the first left column. You will then find the corresponding electrical data on the same row than your power plant supply.

EX: Your power plant supply is 460V at 60 Hz. According to the table, you will then get these values:

PLANT POWER SUPPLY: 460 Volts - 60 Hertz

TOTAL HORSEPOWER: 50.5

TOTAL KILOWATTS: 37.6

<u>CONTROL PANEL TRANSFORMER</u>: 1500 volt-amps

BRANCH CIRCUIT DISTRIBUTION SWITCH: 100 amp

BRANCH CIRCUIT FUSE RECOMMENDED (FRS-R): 100 amp

BRANCH CIRCUIT FEEDER RECOMMENDED (THHN): 4 AWG (21.6mm²)


BRANCH CIRCUIT FEEDER CONDUIT RECOMMENDED: 1 in.(25mm)


SHORT CIRCUIT INTERRUPTING CAPACITY: 200,000 AIC

466371F9901US F1 12SE00 jx



OVERALL DIMENSIONS:







SUMMARY OF ACOUSTICS

Files #	Files # + MEM # Frq.		Frq.	Condition Distance		Overall		< 550Hz		> 550Hz	
			•			С	Α	С	Α	С	Α
1.	+	1/21	5 kHz	Start of cycle	0.5m	112	111	109	100	110	110
2.	+	2/22	5 kHz	End of cycle	0.5m	116	114	112	105	113	114
3.	+	3/23	5 kHz	Start of cycle	0.5m						
4.	+	4/24	1 kHz	End of cycle	0.5m						
5.	+	5/25	5 kHz	Start of cycle	1.0m	111	108	108	98	107	107
6.	+	6/26	5 kHz	End of cycle	1.0m	114	111	112	103	110	110
7.	+	7/27	1 kHz	Start of cycle	1.0m						
8.	+	8/28	1 kHz	End of cycle	1.0m						
9.	+	9/29	5 kHz	Start of cycle	2.0m	110	106	108	96	105	105
10.	+	10/30	5 kHz	End of cycle	2.0m	110	109	109	99	108	108
11.	+	11/31	1 kHz	Start of cycle	2.0m						
12.	+	12/32	1 kHz	End of cycle	2.0m						
13.	+	13/33	5 kHz	Start of cycle/ no pallet	0.5m	113	112	108	103	112	112
14.	+	14/34	5 kHz	End of cycle/ no pallet	0.5m	110	108	107	102	106	106
15.	+	15/35	1 kHz	Start of cycle/ no pallet	0.5m						
16.	+	16/36	1 kHz	End of cycle no pallet	0.5m						

Table C SUMMARY OF ACOUSTICS.

466371F9901US F1 12SE00 xi

Specifications

SUPERPAC INSTALLATION MANUAL



Xİİ 466371F9901US F1 12SE00



PREPARATION

The SUPERPAC stands on a base plate that is fixed on beams. Those beams are fortified in a concrete slab and this platform must be placed in the floor. Use this section with the *Foundation drawing* (# 472891) and the *Installation drawing* (# 472890) to prepare the location and to install the SUPERPAC. This section is not a replacement of the two drawings listed above; it is presented here for complementary information.

PREPARING THE LOCATION OF THE SUPERPAC

- 1. The framework should be prepared according to specifications presented in figure 1.1, 1.2 and 1.3.
- 2. The 15' x 15' [4572mm x 4572mm] framework must be surrounded by a 3/4" [19mm] thick strip of rigid type insulating board around SUPERPAC concrete base to isolate vibration.
- The length, width and thickness of the foundation specified in figures 1.1 and 1.2 represent minimum dimensions. The SUPERPAC foundation can be increased in length, width or thickness to accommodate existing soil conditions.

Note: The concrete foundation dimensions should **never** be less than the dimensions specified.

4. A I-beam should be installed. It is used as a rear support. It should be 7'-8" long.




Figure 1.1 SIDE ELEVATION.

Superpac INSTALLATION MANUAL



- 5. Cut the I-beams to proper length (see table 1.3).
- 6. Weld the I-beams together.

Note: 3/4" [19mm] reinforced steel bars should be welded to the I-beams going in various directions to give added support and anchorage to the machine. It should be sufficient to maintain beams in place while concrete is being poured.

desired height. For recommended beam size relative to the desired distance between the base plate and the floor, consult table 1.3 below.

IMPORTANT! The centerline of the machine is not the same as the center of the concrete slab. The centerline of the block machine is offset to one side of the foundation (see figure 1.2).

8. Place concrete to make base. We recommend a minimum 4000 psi (275 bar) concrete.

7. Place the beams (including rear support) at the

DISTANCE FROM FLOOR TO BOTTOM OF BASE PLATE DIMENSION (A) INCHES & [mm]	HEIGHT OF BEAM IN CONCRETE DIMENSION (B) INCHES & [mm]	WIDTH OF BEAM DIMENSION (C) INCHES & [mm]	SIZE AND WEIGHT OF BEAM RECOMMENDED INCHES & LBS/FT	SIZE AND WEIGHT OF BEAM IN CONCRETE mm & Kg/m
1 [25] 2 [51] 3 [76] 4 [102] 5 [127] 6 [152] 7 [178]	11 [279] 10 [254] 9 [229] 8 [203] 10 [254] 9 [229] 8 [203]	5 [25] 5 [51] 5 [76] 5 [102] 5.5 [127] 5.5 [152] 5.5 [178]	S12 @ 31.8 #/FT S12 @ 31.8 #/FT S12 @ 31.8 #/FT S12 @ 31.8 #/FT S15 @ 42.9 #/FT S15 @ 42.9 #/FT S15 @ 42.9 #/FT S15 @ 42.9 #/FT	S305 @ 47.3 Kg/m S305 @ 47.3 Kg/m S305 @ 47.3 Kg/m S305 @ 47.3 Kg/m S381 @ 63.8 Kg/m S381 @ 63.8 Kg/m S381 @ 63.8 Kg/m S381 @ 63.8 Kg/m
8 [203] 9 [229]	10 [254] 9 [229]	6 [203] 6 [229]	S18 @ 54.7 #/FT	S457 @ 81.4 Kg/m

Table 1.3




Figure 1.2 FRONT ELEVATION.



 The electrical panel can be installed on any side of the machine but is usually installed on the opposite side of unloader (see figure 1.4). It can also be installed in any location to accommodate specific plant layout.

Note: To comply with articles 110-9 and 110-10 of the national electrical code, American customers shall supply a branch circuit protective device to feed this control. The protective device shall have a short circuit interrupting rating of no less than the available short circuit current. Failure to do so could result in a rupture of the protective device while attempting to clear a fault. Besser Company recommends the use of protective devices with interrupting ratings of no less than 200,000 AMPS RMS symmetrical. See the electrical data chart on drawing #439096 for recommended protection. [As for customers outside the US, please check with your country's electrical codes and make sure

you comply with all laws concerning electrical devices.]

- 10. Conduits for electrical panel can be installed as shown on figures 1.4 and 1.5.
- 11.A conduit for the resocoder must also be installed as shown on figure 1.5.
- 12. The Graphic Control Station has to be connected to the electrical panel. Run conduit from electrical panel to display control station. The conduit wire length can not be greater than 45 linear feet [13.7 meters]. The location is shown on the plant layout drawing.




Figure 1.3 3-D VIEW.



Note: Refer to table 1.3 for "C" value.




Figure 1.4 TOP VIEW.



- 13. Once the frame is properly located and leveled, pour concrete inside within 1 1/2" [38mm] of top of I-beam to allow for machine grouting. Do not pour the concrete up to the top of the beams. This also includes the area of concrete between the I-beams. Refer to figure 1.3.
- **Note:** The top of the I-beams needs to be level (within 1/64" [0.4mm]) around the elevation given on the installation prints. For optimum equipment performance, these steel frames need to be level and at the proper elevation.




Figure 1.5 DETAIL VIEW OF BLOCK MACHINE ELECTRICAL PANEL.



MACHINE HANDLING

The figure below shows where the machine should be hooked for handling.




Figure 1.6 MACHINE HANDLING.



INSTALLATION




Figure 1.7 TYPICAL SUPERPAC INSTALLATION.

Superpac INSTALLATION MANUAL



TO INSTALL A SUPERPAC:

Establish center lines for machine.

Note: The centerline of the machine **is not** the same as the center of the concrete slab. The centerline of the block machine is offset to one side of the foundation as shown in figure 1.2.

- 2. Clean area inside support steel and top of steel.
- 3. Make sure a 3/4" [19mm] strip of insulation has been placed between the machine foundation and the plant floor to isolate the vibration to the machine foundation (figure 1.3).
- 4. Place machine on support steel and align with center lines.
- Level machine using machined area next to side plates to within 1/32" [0.8mm]. Use 6" [152mm] shim every foot [305mm]. Check machine vertical

- level on both slide shafts (must be plumb both ways). Refer to figures 1.8 and 1.9.
- Weld machine to steel with 5/8" [16mm] skip weld.
 Make sure machine stays aligned with center line during welding. Weld over the shims. Refer to figure 1.8 and 1.9.
- Non-shrink grout should be placed inside the Ibeams once the block machine has been placed and test run (figure 1.10). 5.4 cu.ft. (1.64 m³) of grout is necessary for every inch below the base.
- Make air connections. (Refer to figure 1.11 on page 18)
 - a. 50 SCFM at 80 psi [5.5 bars] on the right side of machine for air compaction.
 - b. 10 SCFM at 80 psi [5.5 bars] on the left side of machine for other machine components.




Figure 1.8 RIGHT SIDE ELEVATION.

1-8

Superpac INSTALLATION MANUAL




Figure 1.9 FRONT ELEVATION.






Figure 1.10 POUR NON-SHRINK GROUT INSIDE. FILL-UP TO TOP OF MACHINE BASE PLATE.






Figure 1.11 AIR SUPPLY CONNECTIONS.